

**ADDENDUM NO. 2  
July 26, 2017**

**TO: PLANS AND SPECIFICATIONS FOR**

**CHARM VILLA DRIVE STORMWATER IMPROVEMENTS  
PROJECT 2017-201-1**

Bidders are hereby informed that the construction plans and/or specifications are modified as follows:

**PLANS**

The top of curb elevations at the two **existing inlets** are as follows:

West Inlet: 769.98'  
East Inlet: 770.11'

Elevations are not provided for the three new inlets due to the minimal design done for the project and the desire of the county to adjust curb elevations in the field as described in the pre-bid meeting minutes.

Generally speaking the top of curb of the new inlet on the east side of the road will be at approximately the existing top of curb elevation. The new inlet on the west side of the road will be at approximately the same elevation as the inlet on the east. The new top of curb of the southern-most inlet on the west side of the road may be adjusted upward and it is not in the same location as the existing inlet on the west side of the road.

Bidders should make their own estimation of how deep all inlets will be.

BY THE ORDER OF:

Eric Landwehr, P.E., County Engineer  
Cole County Department of Public Works  
July 26, 2017