

ADDENDUM No. 1
TANNER BRIDGE ROAD
SAFETY IMPROVEMENTS PROJECT – PHASE 1
Project No. 2017-601-1
COLE COUNTY DEPARTMENT OF PUBLIC WORKS
August 27, 2019

Notice is hereby given to bidders that in reference to the subject project, the following modifications shall be noted. All other aspects of the Contract Documents remain in full force and effect.

PRE BID MEETING MINUTES

The minutes from the pre-bid meeting held on August 22, 2019 are attached and shall be included as part of the bidding documents.

BID PROPOSAL FORM CHANGES

The following changes have been made to the bid proposal form. **A revised bid proposal is attached.** The Bidder shall use the revised bid proposal form when preparing his bid.

- Underground utility sleeves have been added to the bid proposal for reasons discussed in the pre-bid minutes.
- 6" Asphalt Drive bid item has been removed
- 6" Concrete Drive bid item quantity has been increased

PLAN SHEET CHANGES

The driveway at 11+96.33 LT has been changed from asphalt to concrete. All associated items on the plans shall be changed to reflect this.

JOB SPECIAL PROVISIONS CHANGES:

The Bidder shall replace Job Special Provision **F. Liquidated Damages / Liquidated Savings for Completion Date** with the one listed below:

F. TIME FOR COMPLETION OF WORK / LIQUIDATED SAVINGS FOR EARLY COMPLETION

1.0 Description. Completion of this contract shall be in accordance with Sec. 108.7 and will be administered on a completion date as well as a calendar days basis.

1.1 Regardless of when the work is begun on this contract, all work shall be completed on or before the date specified below. Completion by this date shall be in accordance with the requirement of Sec. 108.7.

Completion Date: May 30, 2020

2.0 Closure Days. Tanner Bridge Road may not be closed to thru traffic more than the number of calendar days listed below.

Closure Days: 30

3.0 Should the contractor, or in case of default, the surety, fail to complete the work within the above specified calendar days or the completion date, whichever occurs first, a deduction of the amount shown below will be made for each day that the contract remains uncompleted in accordance with the requirements of Sec. 108.8. These damages are in addition to any other damages as specified elsewhere in this contract.

Liquidated Damages per Day: \$700

4.0 Liquidated Savings for Early Completion. The Contractor may receive an incentive payment from the County, in addition to all other sums earned under the contract, if the project is substantially complete in November 2019. An incentive payment of **\$10,000** will be made if the work described above is substantially completed on or before **November 30, 2019**. Substantial completion shall be considered as completion of all work on all bid items with the exception of fence and gates.

4.1 In the event of an excusable delay, an extension of the contract completion time will not extend the date specified for determining any liquidated savings or incentive. Further, in the event of an excusable delay, if the Contractor completes the work providing for liquidated savings or incentive on or before the completion date, that shall not constitute a basis to claim acceleration costs in addition to the liquidated savings or incentive that may be earned.

4.2 The incentive payment described is made, not as bonus or gift, but as stipulated compensation in full for reduced risks, delay and inconvenience experienced by the traveling public, and for other reduced costs to the County and the public resulting from early completion.

5.0 Revise Section 108.8.1.2 (a) and (b) and substitute the following for this project:

- a. Liquidated damages will be assessed from December 15 to March 15.
- b. Liquidated damages will be assessed for Saturdays, Sundays, and Holidays.

The Bidder shall add the following Job Special Provision:

V. UNDERGROUND UTILITY SLEEVES

1.0 The Contractor shall install 4 inch diameter Schedule 40 PVC pipe under the Lutz driveway at locations directed by Three Rivers Electric and Centurylink. The pipe shall be clearly marked on each end for future locating. Each sleeve shall be paid for at the contract unit price which will include all equipment, labor and materials including the pipe to complete the installation as well as all other incidental work or material. It is expected that mechanical chipping of rock will be required to install these sleeves.

DOCUMENTS ATTACHED FOR REFERENCE

**Updated Bid Proposal
Minutes from Pre-Bid Meeting held November 22, 2019**

BY THE ORDER OF:

Eric Landwehr, P.E., County Engineer
Cole County Department of Public Works

Enclosures