

**ADDENDUM NO. 1**

**KLEFFNER RIDGE PAVEMENT REPLACEMENT  
PROJECT NO. 2023-505-1**

**COLE COUNTY DEPARTMENT OF PUBLIC WORKS  
November 1, 2023**

**QUESTIONS AND ANSWERS**

Received by telephone, e-mail etc. prior to issuing Addendum No. 1.

**Q1.** What is the typical section for the pavement replacement?

**A1.** The existing concrete shall be replaced with 6" of concrete pavement over 4" of Type 5 Aggregate Base. The concrete shall be an approved 4,000 psi mix.

**Q2.** Does the contractor need to dowel the new pavement into the existing?

**A2.** Yes. All joints between existing and new pavement shall be doweled with 1/2" x 24" dowel bars. Transverse joints shall have dowel bars spaced at 12" and longitudinal joints shall have dowel bars spaced at 30". Meeting held March 2, 2023.

**END OF ADDENDUM NO. 1**